



定格総荷重表 450t吊クローラークレーン(7450)

単位:t

ブーム長さm 作業半径m	18.29m	24.38m	30.48m	36.58m	42.67m	48.77m	54.86m	60.96m	67.06m	73.15m	79.25m
8.0	335.0	335.0	330.0								
9.0	295.0	295.0	295.0								
10.0	263.0	263.0	263.0	261.9							
12.0	208.0	206.0	206.0	205.1	201.0	198.3					
14.0	165.9	165.9	165.9	165.7	164.2	161.9	159.5	157.3			
16.0	136.3	136.2	136.1	135.8	135.5	135.9	133.9	131.8	130.0	120.8	99.0
18.0	115.2	115.2	114.9	114.5	114.2	114.5	114.2	112.8	111.1	109.4	99.0
20.0		99.5	99.0	98.5	98.2	98.5	98.1	97.6	96.5	94.8	93.4
22.0		99.5	86.7	86.1	85.7	86.0	85.6	85.1	84.6	83.2	81.9
24.0		87.2	76.8	76.2	75.8	76.0	75.6	75.1	74.6	73.8	72.5
26.0			68.8	68.1	67.7	67.8	67.4	66.9	66.3	65.7	64.6
28.0				62.1	61.4	60.9	61.1	60.6	60.0	59.5	58.8
30.0					55.8	55.2	55.3	54.9	54.3	53.7	53.0
34.0						46.2	46.2	45.7	45.0	44.5	43.7
38.0							39.3	39.3	38.7	38.0	37.4
42.0								33.9	33.2	32.5	31.9
46.0									28.9	28.1	27.4
50.0										24.4	23.7
54.0											20.8
58.0											20.3
62.0											17.1
66.0											13.5
66.0											10.5
フックブロック質量 (ton)											
フックの容量 ton	450	230	100	50	16.5						
質量 ton	8.4	4.6	2.8	1.9	0.94						

第15吉野号 (450t吊搭載)

第15吉野号	尺度 1:500
KB7450定格総荷重表	H24.07.01
吉野建設株式会社	